



SERVICE BULLETIN No.1129

Circulate to the owners and operators of the units listed
In the Service Information section of this Bulletin

COACH MODEL	: T2145 and C2045
BULLETIN TYPE	: Product Improvement
MANUAL & SECTION	: Operator's Guide Book: Section 2 – Operating Instructions Spare Parts Manual: N/A
PARTS BOOK REVISION	: No
DATE	: April 29, 2005
SUBJECT	: ADA platform lift interlock – warning lamp lens
TERMS & CONDITIONS	: No claims will be accepted with reference to this Bulletin

APPLICATION:

The red "Lift Power On" warning lamp lens subject of this Bulletin has been cut into production as from following units:

Model	Engine	VIN
T2145	Cummins	44300 →
	Detroit Diesel	44610 →
C2045	Cummins	45441 →
	Detroit Diesel	45930 → 45934; 45954 →

DESCRIPTION:

As from the above-mentioned coach models the interlock system has been changed. As one of the safety enhancements in addition to the already existing safety features installed on these vehicles, the color of the "lift power on" warning lamp on the dashboard has been changed to red.

This modification is also recommended by Van Hool to improve the performance of coaches in the field. A free red warning lamp lens and a retrofit procedure are being provided with this Bulletin.

Service personnel: please read, initial and circulate.

Service Manager	Parts Manager	Warranty Administrator	Workshop Foreman	Service Technician

PARTS AND PRODUCTS:

New parts

Part No.	Description	Qty.
VH 660792544	Lift power 'on' warning lamp lens, red	1

- A free red lift power 'on' warning lamp lens has been included with this Bulletin.
- Parts and products disposition: discard according to applicable environmental regulations.

PROCEDURE:

If you do not have the expertise to perform present procedure, do not hesitate to go to your nearest ABC Customer Care & Parts Source dealership.

1. General:

- For your information only: the time required to change the warning lamp lens is approximately 0.25 hours.
- This job should be executed by an experienced automotive electrician.
- For more information on your coach's wiring, refer to the Electrical Wiring Diagram Booklet, which has been supplied with the vehicle.

2. Special tools, equipment or services:

- To do this job, no special tools, equipment or services are required.


3. Preparations:

- Park the coach on a level surface with the front wheels straight.
Apply the parking brake and shut down the engine.
- Switch off all systems and turn off the battery master switch.
- Read the entire procedure before beginning to work.

CAUTION: Observe safe shop practices at all times.

4. Installation guidelines:

- 1) Locate the ADA platform lift interlock warning lamp on the dashboard (see Figure 1).



- 2) Undo and remove the screws securing the top cover of the dashboard (C2045 only).
Withdraw the top cover.
- 3) Undo and remove the screws securing the switch panel to the dashboard frame.
- 4) Pull-back the switch panel. The warning lamp holder is snap fit. Remove it by pressing the two locking tangs.
- 5) Withdraw the warning lamp.
- 6) The warning lamp lens is press fit in the lamp holder. Using a small flat blade screwdriver, push out the OE lens from behind.
- 7) Install the new lens by pressing it in the now vacant aperture.
- 8) Reinstall the warning lamp.
- 9) Reinstall the lamp holder in the switch panel.
- 10) Reinstall the switch panel.
- 11) Reinstall the dashboard top cover (C2045 only).

Procedure complete.

DISCLAIMER:

The installation guidelines contained herein are not exclusive. Van Hool cannot possibly know, evaluate, or advise the transportation industry of all conceivable ways in which the installation may be undertaken or of the possible consequences of each such installation. Other installations may be as good, or better, depending upon the particular circumstances involved.

Each carrier who uses the installation guidelines herein must first satisfy itself thoroughly that neither the safety of its employees or agents, nor the safety or usefulness of any products, will be jeopardized by any installation selected.

SERVICE INFORMATION:

1. Service Bulletins are issued to supplement or supersede information in the Van Hool manuals. Note Service Bulletin number, date and subject on the register at the end of the relevant chapter(s). File Service Bulletin separately for future reference.
2. Units eligible for free parts covered by this Bulletin:

18551, 24501, 24593, 24823, 24975, 25000, 28464, 29482 → 29484, 29487, 29721 → 29726, 29951 → 29952, 40141, 43019 → 43020, 43077, 43240, 43320 → 43324, 43406, 43408 → 43409, 43429 → 43431, 43544 → 43548, 43560, 43633 → 43634, 43751 → 43757, 43810, 43937, 43943 → 43944, 43963, 43965, 43977, 44096 → 44100, 44102, 44132, 44248 → 44251, 44278 → 44281, 44521 → 44522, 44537, 44547, 44551 → 44552, 44562 → 44566, 44596 → 44600, 45002, 45004, 45041 → 45044, 45174 → 45201, 45203 → 45205, 45217 → 45218, 45220 → 45221, 45253 → 45254, 45256 → 45261, 45281 → 45285, 45310 → 45317, 45319 → 45324, 45342 → 45382, 45404, 45502, 45533 → 45534, 45575 → 45576, 45581 → 45592, 45623 → 45624, 45628 → 45629, 45639 → 45640, 45645 → 45646, 45681 → 45682, 45685, 45711 → 45712, 45714 → 45715, 45717 → 45719, 45741 → 45745, 45765 → 45767, 45769 → 45770, 45772 → 45776, 45780 → 45796, 45798 → 45810, 45812 → 45813, 45816 → 45838

THIS PAGE HAS BEEN LEFT BLANK INTENTIONALLY